BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31094

APPROVED SCHEDULE - B

No. E/BTP/BBMP/E-PMT/02/2018-19, Date: 26.07.2018

Construction and improvements of culverts in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of HEMADRI REDDY ( )	
				In Figures	In Words
1	63	KSRRB M 200-12.1. Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable materail with all lifts complete as per specifications (page No. 137, item No. 18.17)	Cum	307.06	Rupees Three Hundred Seven and Six Paise Only
2	90.72	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m. (P-258,It.37.48)	Cum	170.92	Rupees One Hundred Seventy and Ninety Two Paise Only
3	56.7	KSRB 4-1.3:Providing and layingi n position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications. Specification No.KBS 4.1, 4.2 PWD SR 2016-17 (P-12, It.4.3)	Cum	4836.58	Rupees Four Thousand Eight Hundred Thirty Six and Fifty Eight Paise Only
4	90.72	Reconstruction of size stone masonry with available stones in C.M 1:6 as per direction of the Engineer-in-charge.	Cum	2533.07	Rupees Two Thousand Five Hundred Thirty Three and Seven Paise
5	22.68	KSRB 5.2-3:Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6 stone hammered dressed in courses not less than 20 cms high, bond stones at two m, apart in each course including cost of materials, labour, curing complete as per specifications. PWD SR 2015-16 (P-23, It5.6)	Cum	4239.34	Rupees Four Thousand Two Hundred Thirty Nine and Thirty Four Paise Only
6	35.28	KSRB 4-1.6:Providing and laying in position plain cement concrete of mix M15 with cement @ 240 Kgs, with 20mm and down size graded granite metal coarse aggregtes @ 0.878 cum and line aggregates @ 0.459 cum,machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.KBS 4.1, 4.2 PWD SR 2016-17 (P-12, It.4.6)	Cum	5406.99	Rupees Five Thousand Four Hundred Six and Ninety Nine Paise Only
7	315	Providing and fixing 25 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification (Data Rate Approved)	Sqm	4791.56	Rupees Four Thousand Seven Hundred Ninety One and Fifty Six Paise Only
8	63	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 PWD SR 2013-14 (P-144 & 133, It.No. 17.1)	Cum	99.38	Rupees Ninety Nine and Thirty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

22/10